

GPS #: **0769**

Date Destroyed:

Date Revised: 8/23/1996

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 972/J-2

City / Location: Unin., Orange County

Scale Factor: 0.99995816

Ellipsoid Red. Factor: 0.99996971

Combination Factor: 0.99992787

Convergence Angle: -00 44 57.07196

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 29 47.74800	117 36 48.07224	2127035.126	6146043.115	633.020
2007.00	33 29 47.76488	117 36 48.08815	2127036.85	6146041.79	

References: RSB 161/42-47

Description:

FD 3" I.P. WITH 3 1/4" OCS BRASS MONUMENT STAMPED "RCE 6978 1972 BOUNDARY", FLUSH. LOCATED FROM THE ENTRANCE OF PRIMA DESHECA LANDFILL, FOLLOW A DIRT RD. UPHILL TO THE WEST AND SOUTH 0.4 MILES. THE MONUMENT IS ON THE SOUTH SIDE OF THE RD. (LOCATED ALONG THE PRIMA DESHECA LANDFILL BOUNDARY)

