

**GPS #:** **0776**

Date Destroyed:

Date Revised: 8/23/1996

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 972/J-2

City / Location: Unin., Orange County

Scale Factor: 0.99995801

Ellipsoid Red. Factor: 0.99997565

Combination Factor: 0.99993366

Convergence Angle: -00 45 04.00434

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 29 36.70017	117 37 00.68763	2125932.541	6144960.246	508.821
2007.00	33 29 36.71700	117 37 00.70355	2125934.26	6144958.92	

References: RSB 161/42-47

**Description:**

FD 2" I.P. WITH ALUMINUM OCS CAP STAMPED "RCE 6978 1972 BOUNDARY" DOWN 0.3' IN DIRT. LOCATED FROM THE ENTRANCE OF PRIMA DESHECA LANDFILL, PROCEED EAST AND NORTH 0.2 MILES ON THE DIRT RD. UPHILL TO THE W'LY TOWER. THE MONUMENT IS ON THE FENCE LINE 50' WEST OF THE TOWER.

