

GPS #: 0899

Date Destroyed: 7/25/2000

Date Revised: 7/1/1997

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 951/C-7

City / Location: Laguna Niguel

Scale Factor: 0.99995871

Ellipsoid Red. Factor: 0.99997487

Combination Factor: 0.99993359

Convergence Angle: -00 49 03.84911

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 30 27.08305	117 44 17.15187	2131530.551	6108073.535	525.120
2007.00	33 30 27.09986	117 44 17.16793	2131532.27	6108072.20	

References: OCS SURVEY FILE # G93/94-13N

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 2" I.P. WITH PUNCHED SPIKE AND 1 1/2" BRASS O.C.S. TAG STAMPED "4-94" FLUSH IN DIRT - LOCATED FROM THE INTER OF PACIFIC ISLAND DR. AND TALAVERA DR., PROCEED N'LY, THEN W'LY ALONG TALAVERA DR. TO A LOCKED GATE WITH A GUARD SHACK (ENTRANCE TO A PRIVATE COMMUNITY). PROCEED THRU SAID GATE AND CONTINUE S'LY ALONG MARSEILLE TO ITS INTER WITH LE CONTE, PROCEED S'LY, THEN N'LY ALONG LE CONTE TO ITS END. THE STATION IS LOCATED 130'+/- NW'LY OF THE END OF LE CONTE IN THE DIRT RD. ON THE W'LY SIDE OF RESIDENCE #1.