

GPS #: **0904**

Date Destroyed:

Date Revised: 7/1/1997

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 862/C-7

City / Location: Lake Forest

Scale Factor: 0.99997056

Ellipsoid Red. Factor: 0.99996402

Combination Factor: 0.99993459

Convergence Angle: -00 46 28.28806

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 46.37743	117 39 34.06528	2187724.607	6132805.319	751.960
2007.00	33 39 46.39400	117 39 34.08116	2187726.30	6132804.00	

References: OCS SURVEY FILE # G93/94-13N

Description:

FD PUNCHED SPIKE AND 1 1/2" BRASS O.C.S. TAG STAMPED "GPS 0904" FLUSH ON A.C. SURFACE - LOCATED FROM THE INTER OF LAKE FOREST DR. AND REGENCY LN., PROCEED SE'LY ALONG REGENCY LN. 0.3 MILE TO A LOCKED STEEL GATE (DA1 KEY) ON THE N'LY SIDE OF REGENCY LN. PROCEED THRU SAID GATE AND CONTINUE NE'LY ALONG THE A.C. RD. 0.1 MILE TO A SECOND LOCKED GATE (DA1 KEY), CONTINUE PAST SAID GATE 0.1 MILE TO SAID MONUMENT LOCATED SOUTH OF THE CHAINED LINK WITH BARBED WIRE FENCE.

