

GPS #: **0912R1**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 740/G-4

City / Location: Yorba Linda

Scale Factor: 1.00000128

Ellipsoid Red. Factor: 0.99997912

Combination Factor: 0.99998040

Convergence Angle: -00 50 20.54406

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 53 27.32406	117 46 36.71967	2271202.531	6098300.087	
2007.00	33 53 27.34058	117 46 36.73605	2271204.22	6098298.73	

References: MM 429/13-15, RSB 149/1-9, CR 2007-0952

Description:

FD SPIKE AND WASHER STAMPED "LS 5411", FLUSH, IN LIEU OF PUNCHED SPIKE WITH WASHER STAMPED "LS 2955". MONUMENT WAS RESET PER CORNER RECORD # 2007-0952. MONUMENT IS LOCATED AT THE CENTERLINE INTERSECTION OF YORBA LINDA BLVD. AND VILLAGE CENTER DR.

