

GPS #: 0925R1

Date Destroyed:

Date Revised: 1/18/2001

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 741/F-6

City / Location: Yorba Linda

Scale Factor: 0.99999890

Ellipsoid Red. Factor: 0.99998588

Combination Factor: 0.99998477

Convergence Angle: -00 48 05.18661

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 52 36.03701	117 42 30.39914	2265721.351	6118990.695	
2007.00	33 52 36.05363	117 42 30.41538	2265723.05	6118989.35	

References: MM 614/14-20, RSB 149/1-9, CR 2001-0108

Description:

FD PUNCHED SPIKE AND BRASS 1 1/4" OCS WASHER STAMPED "0925R1 12/00" FLUSH, IN LIEU OF SPIKE AND WASHER STAMPED "RCE 16683". MONUMENT HAS BEEN RESET PER CORNER RECORD # 2001-108. MONUMENT IS LOCATED AT THE CENTERLINE INTER OF BRUSH CANYON DR. AND CAMINO DE BRYANT.

