

GPS #: 0928

Date Destroyed:

Date Revised:

Benchmark Designation: J-167

OCS Index Map: 6LA

Page/Grid: 951/B-7

City / Location: Laguna Beach

Scale Factor: 0.99995892

Ellipsoid Red. Factor: 1.00000390

Combination Factor: 0.99996282

Convergence Angle: -00 49 32.76454

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 30 41.25636	117 45 09.77153	2133026.885	6103639.152	-81.519
2007.00	33 30 41.27333	117 45 09.78756	2133028.62	6103637.82	

References: OCS 1987 VERTICAL CONTROL BOOK

Description:

FD U.S.C.&G.S. BRASS BENCHMARK DISK STAMPED "J-167" FLUSH IN CONC. - LOCATED IN THE NE CORNER OF THE INTER OF PACIFIC COAST HWY. AND COUNTY CLUB RD., IN THE N'LY END OF THE CONC. WING WALL FOR THE BRIDGE OVER ALISO CREEK, 1' LOWER THAN THE HWY.

