

GPS #: 0931

Date Destroyed:

Date Revised: 8/20/2003

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 862/G-6

City / Location: Mission Viejo

Scale Factor: 0.99997127

Ellipsoid Red. Factor: 0.99994773

Combination Factor: 0.99991900

Convergence Angle: -00 45 15.55179

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 40 11.63945	117 37 21.70143	2190128.608	6144025.709	1092.383
2007.00	33 40 11.65611	117 37 21.71695	2190130.31	6144024.42	

References: OCS SURVEY FILE # G93/94-13N

Description:

FD 2" I.P. WITH PUNCHED SPIKE AND 1 1/2" BRASS O.C.S. TAG STAMPED "GPS 0800" FLUSH - LOCATED FROM THE INTER OF GLENN RANCH RD. AND EL TORO RD., PROCEED N'LY ALONG EL TORO RD. 0.3 MILE TO AN A.C. RD. WITH A WROUGHT IRON GATE ON THE E'LY SIDE OF THE RD. (ADDRESS 19922/19916). PROCEED E'LY THRU SAID GATE, UP THE A.C. RD. 0.2 MILE TO A "T" INTER. PROCEED S'LY UP THE A.C. RD. 300'+/- TO A LARGE CUT GRASSY LOT. HIKE FROM THE S'LY END OF LOT 500'+/- UP THE RIDGE HEADING SOUTH TO SAID STATION.

