

GPS #: **0933**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 826/H-6

City / Location: Seal Beach

Scale Factor: 0.99997777

Ellipsoid Red. Factor: 1.00000520

Combination Factor: 0.99998304

Convergence Angle: -01 00 18.40490

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 42.39585	118 04 44.69366	2213560.700	6005556.690	-108.678
2007.00	33 43 42.41231	118 04 44.71083	2213562.39	6005555.27	

References: OCS SURVEY FILE # H93/94-15N

Description:

FD 2 1/2" I.P. WITH A BRASS O.C.S. CAP STAMPED "SBAP-5" FLUSH - LOCATED FROM THE SUNSET AQUATIC PARK BOAT LAUNCH RAMP, PROCEED N'LY TO A CHAIN LINK FENCE GATE, PROCEED THRU GATE AND ALONG THE DIRT RD. W'LY TO WHERE THE RD. TURNS N'LY AND WITH A WHITE PADDLE JUST OFF THE LEFT EDGE OF THE RD. STATION IS LOCATED 90'+/- S'LY OF THE RD., 4'+/- FROM THE TOP.

