

**GPS #:** **0944**

Date Destroyed:

Date Revised:

Benchmark Designation: F 978 R67

OCS Index Map: 4LB

Page/Grid: 826/H-5

City / Location: Seal Beach

Scale Factor: 0.99997824

Ellipsoid Red. Factor: 1.00000390

Combination Factor: 0.99998221

Convergence Angle: -01 00 30.35597

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 56.35732	118 05 06.44196	2215004.004	6003744.966	-81.578
2007.00	33 43 56.37374	118 05 06.45908	2215005.69	6003743.55	

References: OCS 1987 VERTICAL CONTROL BOOK

**Description:**

FD 3 1/2" BRASS U.S.C. & G.S. BENCHMARK DISK STAMPED "F 978 R67" FLUSH IN CONC. SIDEWALK - LOCATED FROM THE INTER OF PACIFIC COAST HWY. AND ANDERSON ST., PROCEED NW'LY 0.7 MILE TO THE CONC. BRIDGE #55-10-67 OVER ANAHEIM BAY, 35.4' SW OF THE CENTERLINE OF THE HWY., 2.5' SW OF THE NE EDGE OF A CONC. SIDEWALK ACROSS THE CONC. BRIDGE, 16.7' SE OF THE NW END OF THE WALK, 2.7' NE OF THE GUARD RAIL, SET IN THE TOP OF THE CONC. WALK, 0.8' HIGHER THAN THE HWY.

