

GPS #: **0945**

Date Destroyed:

Date Revised:

Benchmark Designation: 1J-57-80

OCS Index Map: 4LB

Page/Grid: 826/J-6

City / Location: Sunset Beach

Scale Factor: 0.99997733

Ellipsoid Red. Factor: 1.00000530

Combination Factor: 0.99998264

Convergence Angle: -01 00 15.78603

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 29.12194	118 04 39.92790	2212212.101	6005935.622	-109.501
2007.00	33 43 29.13839	118 04 39.94509	2212213.79	6005934.20	

References: OCS 1987 VERTICAL CONTROL BOOK

Description:

FD 3 3/4" O.C.S. ALUMINUM BENCHMARK DISK STAMPED "1J-57-80" FLUSH ON TOP OF 6' X 5.4' EDISON VAULT - LOCATED AT THE INTER OF PACIFIC COAST HWY. AND ANDERSON ST., 85'+/- NE OF THE HWY., 35'+/- NW OF THE MEDIAN OF ANDERSON ST., SET FLUSH ON TOP OF 6' X 5.4' EDISON VAULT, 3.0' BACK OF CURB FACE.

