

GPS #: **0970**

Date Destroyed:

Date Revised: 2/23/1997

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 992/E-2

City / Location: San Clemente

Scale Factor: 0.99995594

Ellipsoid Red. Factor: 0.99999983

Combination Factor: 0.99995577

Convergence Angle: -00 46 01.73911

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 26 34.55108	117 38 45.75209	2107641.316	6135816.931	3.468
2007.00	33 26 34.56806	117 38 45.76772	2107643.05	6135815.63	

References: OCS FILE # OT96/7-3, GEODETIC UNIT

Description:

FD PUNCHED SPIKE & 1 1/2" OCS BRASS TAG
STAMPED "GPS 0970" FLUSH IN A.C. LOCATED AT
THE APPARENT CENTERLINE OF LA VENTANA 290'
+/- SE'LY OF MONTE VISTA.

