

GPS #: 0980

Date Destroyed:
Date Revised: 11/19/1998
Benchmark Designation:
OCS Index Map: 5LB
Page/Grid: 861/H-3
City / Location: Unin., Orange County

Scale Factor: 0.99997326
Ellipsoid Red. Factor: 0.99997484
Combination Factor: 0.99994810
Convergence Angle: -00 47 39.19023

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 19.56548	117 41 43.09150	2197292.455	6122031.245	525.809
2007.00	33 41 19.58196	117 41 43.10746	2197294.14	6122029.92	

References: Survey File # 989OP5307

Description:

FOUND 3 1/2" OCS BRASS DISK DOWN 0.9' IN 6" DIAMETER ALUMINUM WELL MONUMENT LOCATED ON TOP OF A.C. DAM. MONUMENT IS LOCATED FROM THE INTERSECTION OF IRVINE BOULEVARD AND N STREET, PROCEED NORTHEASTERLY ALONG N STREET 0.6 MILES TO THE AGUINAGA FERTILIZER COMPANY OFFICE ON LEFT. CONTINUE EASTERLY ALONG SAID ROAD INTO THE PACIFIC COAST NURSERY 0.2 MILES TO GRAVEL ROAD ON RIGHT. TURN RIGHT AND PROCEED THRU AND AROUND THE NURSERY 1.0 MILE TO DAM LOCATED ON RIGHT. MONUMENT IS LOCATED ON THE NORTHERLY END OF DAM.

