

GPS #: 0981

Date Destroyed:

Date Revised: 11/19/1998

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 861/H-3

City / Location: Unin., Orange County

Scale Factor: 0.99997322

Ellipsoid Red. Factor: 0.99997482

Combination Factor: 0.99994804

Convergence Angle: -00 47 38.34363

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 18.40856	117 41 41.55088	2197173.720	6122159.791	526.236
2007.00	33 41 18.42509	117 41 41.56679	2197175.41	6122158.47	

References: Survey File # 989OP5307

Description:

FOUND 3 1/2" OCS BRASS DISK DOWN 0.9' IN 6" DIAMETER ALUMINUM WELL MONUMENT LOCATED ON TOP OF A.C. DAM. MONUMENT IS LOCATED FROM THE INTERSECTION OF IRVINE BOULEVARD AND N STREET, PROCEED NORTHEASTERLY ALONG N STREET 0.6 MILES TO THE AGUINAGA FERTILIZER COMPANY OFFICE ON LEFT. CONTINUE EASTERLY ALONG SAID ROAD INTO THE PACIFIC COAST NURSERY 0.2 MILES TO GRAVEL ROAD ON RIGHT. TURN RIGHT AND PROCEED THRU AND AROUND THE NURSERY 1.0 MILE TO DAM LOCATED ON RIGHT. MONUMENT IS LOCATED 70' +/- NORTHERLY OF SPILLWAY.

