

GPS #: **0982**

Date Destroyed:

Date Revised: 11/19/1998

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 861/H-3

City / Location: Unin., Orange County

Scale Factor: 0.99997320

Ellipsoid Red. Factor: 0.99997483

Combination Factor: 0.99994803

Convergence Angle: -00 47 37.77536

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 17.63166	117 41 40.51676	2197093.987	6122246.076	525.904
2007.00	33 41 17.64822	117 41 40.53273	2197095.68	6122244.75	

References: Survey File # 989OP5307

Description:

FOUND 3 1/2" OCS BRASS DISK DOWN 0.9' IN 6" DIAMETER ALUMINUM WELL MONUMENT LOCATED ON TOP OF A.C. DAM. MONUMENT IS LOCATED FROM THE INTERSECTION OF IRVINE BOULEVARD AND N STREET, PROCEED NORTHEASTERLY ALONG N STREET 0.6 MILES TO THE AGUINAGA FERTILIZER COMPANY OFFICE ON LEFT. CONTINUE EASTERLY ALONG SAID ROAD INTO THE PACIFIC COAST NURSERY 0.2 MILES TO GRAVEL ROAD ON RIGHT. TURN RIGHT AND PROCEED THRU AND AROUND THE NURSERY 1.0 MILE TO DAM LOCATED ON RIGHT. TO GET TO THE SOUTHERLY SIDE OF DAM, PROCEED ALONG A.C. ROAD LOCATED 250' +/- DOWNSTREAM OF DAM. MONUMENT IS LOCATED 5" +/- SOUTHERLY OF SPILLWAY.

