

**GPS #:** **0983**

Date Destroyed:

Date Revised: 11/19/1998

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 861/H-3

City / Location: Unin., Orange County

Scale Factor: 0.99997316

Ellipsoid Red. Factor: 0.99997483

Combination Factor: 0.99994799

Convergence Angle: -00 47 37.32416

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 16.34815	117 41 39.69566	2196963.301	6122313.653	526.052
2007.00	33 41 16.36477	117 41 39.71148	2196965.00	6122312.34	

References: Survey File # 989OP5307

**Description:**

FOUND 3 1/2" OCS BRASS DISK DOWN 0.9' IN 6" DIAMETER ALUMINUM WELL MONUMENT LOCATED ON TOP OF A.C. DAM. MONUMENT IS LOCATED FROM THE INTERSECTION OF IRVINE BOULEVARD AND N STREET, PROCEED NORTHEASTERLY ALONG N STREET 0.6 MILES TO THE AGUINAGA FERTILIZER COMPANY OFFICE ON LEFT. CONTINUE EASTERLY ALONG SAID ROAD INTO THE PACIFIC COAST NURSERY 0.2 MILES TO GRAVEL ROAD ON RIGHT. TURN RIGHT AND PROCEED THRU AND AROUND THE NURSERY 1.0 MILE TO DAM LOCATED ON RIGHT. TO GET TO THE SOUTHERLY SIDE OF DAM, PROCEED ALONG A.C. ROAD LOCATED 250' +/- DOWNSTREAM OF DAM. MONUMENT IS LOCATED ON THE SOUTHERLY END OF DAM.

