

GPS #: **0984**

Date Destroyed:

Date Revised: 8/18/1998

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 861/J-7

City / Location: Lake Forest

Scale Factor: 0.99997057

Ellipsoid Red. Factor: 0.99997859

Combination Factor: 0.99994917

Convergence Angle: -00 47 26.69908

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 46.56869	117 41 20.36038	2187866.657	6123822.061	447.414
2007.00	33 39 46.58545	117 41 20.37640	2187868.37	6123820.73	

References: MM 647/23-32

Description:

FD PUNCHED ROUND HEAD SPIKE WITH 1 1/2" BRASS WASHER STAMPED "LS 4965" FLUSH IN A.C. LOCATED AT THE CENTERLINE INTER OF BAKE PKWY. AND CRESENT BAY.

