

GPS #: 1001

Date Destroyed:

Date Revised: 2/23/1997

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 800/J-3

City / Location: Orange

Scale Factor: 0.99998546

Ellipsoid Red. Factor: 0.99997734

Combination Factor: 0.99996280

Convergence Angle: -00 49 47.54163

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 16.86325	117 45 36.66256	2233684.709	6102820.091	473.490
2007.00	33 47 16.87949	117 45 36.67885	2233686.37	6102818.74	

References: RSB 136/41-44

Description:

FD 2" IP, WITH NAIL AND TIE TAG STAMPED "LS 5780", FLUSH IN DIRT MEDIAN, LOCATED ALONG THE CENTERLINE AT THE BC ON JAMBOREE RD., 0.3 +/- MILES S'LY FROM ITS INTER WITH SANTIAGO CANYON RD.

