

GPS #: **1003**

Date Destroyed:

Date Revised: 2/23/1997

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 800/J-3

City / Location: Orange

Scale Factor: 0.99998613

Ellipsoid Red. Factor: 0.99997587

Combination Factor: 0.99996199

Convergence Angle: -00 49 49.55087

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 34.18329	117 45 40.31893	2235439.765	6102536.894	504.297
2007.00	33 47 34.19957	117 45 40.33526	2235441.43	6102535.54	

References: RSB 136/41-44

Description:

FD GEAR SPIKE AND LARGE TAG STAMPED "LS 5780" FLUSH IN AC, LOCATED ALONG CENTERLINE AT THE BC OF JAMBOREE RD., 180' +/- N'LY FROM ITS INTER WITH SANTIAGO CANYON RD., IN THE LEFT LN. TURN POCKET.

