

GPS #: 1017

Date Destroyed:

Date Revised: 7/10/2001

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 771/D-1

City / Location: Anaheim Hills

Scale Factor: 0.99999566

Ellipsoid Red. Factor: 0.99996764

Combination Factor: 0.99996330

Convergence Angle: -00 48 36.32178

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 51 24.14937	117 43 27.05825	2258522.437	6114111.183	676.281
2007.00	33 51 24.16601	117 43 27.07505	2258524.14	6114109.79	

References: MM 709/39-41, CR 1998-0420

Description:

FD LARGE PUNCHED ROUND HEAD SPIKE WITH 1 1/2" BRASS WASHER STAMPED "RCE 28946" FLUSH IN A.C. AT THE CENTERLINE INTER OF OAK CANYON DR. AND GOLD DUST LN.

