

GPS #: 1026

Date Destroyed: 7/25/2000

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 738/B-1

City / Location: La Habra

Scale Factor: 1.00000580

Ellipsoid Red. Factor: 0.99999180

Combination Factor: 0.99999767

Convergence Angle: -00 56 55.60880

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

| Epoch Adjustment | Latitude | Longitude | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35 | 33 55 02.53386 | 117 58 35.64977 | 2281771.224 | 6037859.766 | 172.756 |
| 2007.00 | 33 55 02.55000 | 117 58 35.66714 | 2281772.88 | 6037858.33 | |

References: RS 92-1117

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED SPIKE AND O.C.S. WASHER STAMPED "STA 34B-AUX" FLUSH IN A.C. LOCATED FROM THE INTER OF IMPERIAL HWY. AND SPRING MEADOW DR., PROCEED W'LY ALONG IMPERIAL HWY. 430'+/- TO SAID STATION LOCATED ALONG THE APPARENT CENTERLINE OF THE HWY. AT THE LOS ANGELES / ORANGE COUNTY LINE.