

GPS #: **1027**

Date Destroyed: **7/26/2000**

Date Revised:

Benchmark Designation:

OCS Index Map: **3L**

Page/Grid: **708/B-7**

City / Location: **La Habra**

Scale Factor: **1.00000660**

Ellipsoid Red. Factor: **0.99999189**

Combination Factor: **0.99999852**

Convergence Angle: **-00 56 55.58637**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 55 17.94428	117 58 35.60896	2283328.756	6037889.000	170.807
2007.00	33 55 17.96050	117 58 35.62637	2283330.42	6037887.56	

References: **RS 92-1117**

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED SPIKE AND WASHER (ILLEGIBLE), DOWN 0.1' IN A.C., ALSO BEING 3.00' EAST OF ANOTHER PUNCHED SPIKE AND WASHER. STATION IS LOCATED FROM THE INTER OF WOODBRIER DR. AND RIDGEHAVEN, PROCEED 200'+/- W'LY ALONG WOODBRIER DR. TO SAID STATION LOCATED ALONG THE APPARENT CENTERLINE OF THE DR. AND ALONG THE LOS ANGELES / ORANGE COUNTY LINE.