

GPS #: 1033R1

Date Destroyed:

Date Revised: 4/3/2001

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 708/B-4

City / Location: La Habra

Scale Factor: 1.00001070

Ellipsoid Red. Factor: 0.99998852

Combination Factor: 0.99999923

Convergence Angle: -00 56 55.48066

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



| Epoch Adjustment | Latitude | Longitude | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35 | 33 56 38.40658 | 117 58 35.41659 | 2291461.150 | 6038039.887 | |
| 2007.00 | 33 56 38.42285 | 117 58 35.43398 | 2291462.82 | 6038038.45 | |

References: RS 92-1117, CR 2001-0691

Description:

FD BRASS NAIL AND BRASS TAG STAMPED "LS 4016" FLUSH, IN LIEU OF ROUND HEAD SPIKE AND WASHER. MONUMENT WAS RESET PER CORNER RECORD # 2001-691. MONUMENT IS LOCATED AT THE VISUAL CENTERLINE INTER OF RUSSEL ST. AND VALLEY HOME AVE., ALONG THE LOS ANGELES / ORANGE COUNTY LINE.

