

GPS #: **1034R1**

Date Destroyed:

Date Revised: 4/3/2001

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 708/A-4

City / Location: Whittier, Los Angeles Co.

Scale Factor: 1.00001070

Ellipsoid Red. Factor: 0.99999072

Combination Factor: 1.00000140

Convergence Angle: -00 57 10.71188

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 56 38.37477	117 59 03.13403	2291496.687	6035704.953	
2007.00	33 56 38.39097	117 59 03.15149	2291498.35	6035703.51	

References: RS 92-1117, CR 2001-0690

Description:

FD PUNCHED SPIKE AND WASHER STAMPED "LS 4016" FLUSH, IN LIEU OF PUNCHED SPIKE AND WASHER "NO STAMPING". MONUMENT WAS RESET PER CORNER RECORD # 2001-690. MONUMENT IS LOCATED AT THE E'LY VISUAL CENTERLINE INTER OF RUSSEL ST. AND BOGARDUS AVE., 12' EASTERLY FROM ANOTHER MONUMENT WITH THE SAME CHARACTER KNOWN AS GPS # 1035R1.

