

GPS #: **1035R1**

Date Destroyed:

Date Revised: 4/3/2001

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 708/A-4

City / Location: Whittier, Los Angeles Co.

Scale Factor: 1.00001070

Ellipsoid Red. Factor: 0.99999073

Combination Factor: 1.00000140

Convergence Angle: -00 57 10.79012

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 56 38.37474	117 59 03.27641	2291496.884	6035692.959	
2007.00	33 56 38.39088	117 59 03.29382	2291498.54	6035691.52	

References: RS 92-1117, CR 2001-0689

Description:

FD PUNCHED SPIKE AND WASHER STAMPED "LS 4016" FLUSH, IN LIEU OF PUNCHED SPIKE AND WASHER "NO STAMPING". MONUMENT WAS RESET PER CORNER RECORD # 2001-689. MONUMENT IS LOCATED AT THE W'LY VISUAL CENTERLINE INTER OF RUSSEL ST. AND BOGARDUS AVE., 12' WESTERLY FROM ANOTHER MONUMENT WITH THE SAME CHARACTER KNOWN AS GPS # 1034R1.

