

**GPS #:** **1040**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 800/G-4

City / Location: Orange

Scale Factor: 0.99998502

Ellipsoid Red. Factor: 0.99997141

Combination Factor: 0.99995644

Convergence Angle: -00 50 26.81659

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 05.52479	117 46 48.13425	2232626.646	6096771.593	597.276
2007.00	33 47 05.54085	117 46 48.15057	2232628.29	6096770.24	

References: CR 0270

**Description:**

FD 4" CONC. POST WITH NAIL AND 3/4" BRASS TAG STAMPED "RCE 97 \_\_" DOWN 1.2', LOCATED FROM THE INTER OF COWAN CANYON CIRCLE AND KINGS CROWN RD., PROCEED NW'LY ALONG KINGS CROWN RD. 70'+/- THEN HIKE NE'LY 80'+/- FROM CURB TO THE TOE OF SLOPE AND DIRT TRAIL. PROCEED N'LY UPHILL ALONG TRAIL 300'+/- TO SAID MONUMENT 7'+/- W'LY FROM TRAIL.

