

**GPS #:** **1047**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 800/H-1

City / Location: Orange

Scale Factor: 0.99998870

Ellipsoid Red. Factor: 0.99997793

Combination Factor: 0.99996663

Convergence Angle: -00 50 10.91704

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



| Epoch Adjustment | Latitude       | Longitude       | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35          | 33 48 39.32929 | 117 46 19.20061 | 2242071.995   | 6099351.872  | 461.197               |
| 2007.00          | 33 48 39.34545 | 117 46 19.21728 | 2242073.65    | 6099350.49   |                       |

References: PMB 229/32-34

## Description:

FD 3/4" I.P., NO TAG, SET WOOD PLUG WITH TACK IN PIPE, DOWN 0.2' LOCATED FROM THE INTER OF SANTIAGO CANYON RD. AND ANGEL VIEW TERRACE, PROCEED S'LY ALONG ANGEL VIEW TERRACE AND UPHILL TO THE TERMINUS OF THE CUL-DE-SAC. CONTINUE S'LY ALONG DIRT TRAIL DOWNHILL 250'+/- TO A GRADED PAD. PARK HERE AND CONTINUE ON FOOT S'LY DOWN GRADED SLOPE TO SAID STATION WHICH IS THE SE'LY CORNER OF LOT 3 LOCATED ALONG THE CHAIN LINK FENCE.

