

GPS #: **1048**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 800/H-1

City / Location: Orange

Scale Factor: 0.99998870

Ellipsoid Red. Factor: 0.99997806

Combination Factor: 0.99996676

Convergence Angle: -00 50 10.39191

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 39.33785	117 46 18.24500	2242071.683	6099432.510	458.369
2007.00	33 48 39.35403	117 46 18.26164	2242073.34	6099431.13	

References: PMB 229/32-34

Description:

FD 3/4" I.P., NO TAG, SET WOOD PLUG WITH TACK IN PIPE, DOWN 0.5' LOCATED FROM THE INTER OF SANTIAGO CANYON RD. AND ANGEL VIEW TERRACE, PROCEED S'LY ALONG ANGEL VIEW TERRACE AND UPHILL TO THE TERMINUS OF THE CUL-DE-SAC. CONTINUE S'LY ALONG DIRT TRAIL DOWNHILL 250'+/- TO A GRADED PAD. PARK HERE AND CONTINUE ON FOOT S'LY DOWN GRADED SLOPE TO SAID STATION WHICH IS THE SE'LY CORNER OF LOT 4 LOCATED AT THE ANGLE POINT OF THE CHAIN LINK FENCE.

