

**GPS #:** **1049**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 770/H-7

City / Location: Orange

Scale Factor: 0.99998914

Ellipsoid Red. Factor: 0.99997730

Combination Factor: 0.99996644

Convergence Angle: -00 50 04.10579

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 50.37705	117 46 06.80564	2243173.380	6100413.904	474.310
2007.00	33 48 50.39326	117 46 06.82233	2243175.04	6100412.52	

References: OCS SURVEY FILE # OC94/5-8N

**Description:**

FD 2" I.P. WITH 2 1/4" O.C.S. BRASS DISK STAMPED "VP DAM BM1" UP 0.1' LOCATED FROM THE TERMINUS OF LOLITA ST./VILLA PARK DAM ACCESS GATE, PROCEED 0.15 MILES ALONG SAID ACCESS RD. TO SAID STATION LOCATED 10'+/- E'LY FROM THE E'LY EDGE OF PAVEMENT.

