

GPS #: 1050

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 800/H-1

City / Location: Orange

Scale Factor: 0.99998881

Ellipsoid Red. Factor: 0.99997735

Combination Factor: 0.99996616

Convergence Angle: -00 50 06.40477

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 42.11443	117 46 10.98928	2242343.392	6100048.768	473.224
2007.00	33 48 42.13062	117 46 11.00602	2242345.05	6100047.38	

References: OCS SURVEY FILE # F89-51

Description:

FD 2 1/4" O.C.S. BRASS DISK STAMPED "VP-30 JAN 1980" IN 6" DIA. CONC. COLLAR, UP 0.05' LOCATED FROM THE INTER OF SANTIAGO CANYON RD. AND LOLITA ST., PROCEED E'LY ALONG LOLITA ST., GO THROUGH A CHAIN LINK GATE (DA1 KEY) AND CONTINUE N'LY ALONG SAID RD. WHEN RD. STARTS TO TURN E'LY AT TOP OF DAM AREA, MAKE A SHARP RIGHT TURN SO THAT YOU ARE HEADING S'LY ONTO THE AUXILIARY DAM. PROCEED THROUGH LOCKED WIRE GATE ENTRANCE (DA1 KEY) AND CONTINUE ALONG DIRT RD. TO THE B.C. ALONG THE DAM RD. STATION IS LOCATED 4'+/- E'LY FROM THE W'LY EDGE OF THE RD.

