

GPS #: 1051

Date Destroyed: 7/25/2000

Date Revised:

Benchmark Designation:

OCS Index Map: 2L

Page/Grid: 800/H-1

City / Location: Orange

Scale Factor: 0.99998874

Ellipsoid Red. Factor: 0.99997795

Combination Factor: 0.99996669

Convergence Angle: -00 50 08.26666

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 40.45420	117 46 14.37751	2242179.755	6099760.457	460.737
2007.00	33 48 40.47036	117 46 14.39424	2242181.41	6099759.07	

References: OCS SURVEY FILE # OC94/5-8N

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD LARGE PUNCHED SPIKE FLUSH IN DIRT SHOULDER LOCATED FROM THE INTER OF SANTIAGO CANYON RD. AND AMAPOLA AVE., PROCEED NW'LY ALONG SANTIAGO CANYON RD. 0.4 MILES TO SAID STATION LOCATED IN THE E'LY DIRT SHOULDER, 4'+/- E'LY OF THE E'LY EDGE OF PAVEMENT OF SANTIAGO CANYON RD.