

GPS #: 1052R1

Date Destroyed: 1/6/2014

Date Revised: 1/4/2014

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 830/A-1

City / Location: Tustin

Scale Factor: 0.99998168

Ellipsoid Red. Factor: 0.99999725

Combination Factor: 0.99997893

Convergence Angle: -00 52 03.93161

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 35.32319	117 49 44.86204	2223732.251	6081718.530	
2007.00	33 45 35.33948	117 49 44.87833	2223733.92	6081717.18	

References: RSB 85/47, CR 2002-1147

Description:

DESTROYED PER CR 2002-1147. FD PUNCHED SPIKE WITH BRASS TAG STAMPED "CAL TRANS", FLUSH IN AC IN LIEU OF 2 1/4" PUNCHED STEEL "CALIFORNIA DIVISION OF HWY.S" DISK SET IN CONC. DOWN 1.4' IN WELL MONUMENT. MONUMENT WAS RESET PER CORNER RECORD 2002-1147 LOCATED AT THE CENTERLINE INTER OF 17th ST. AND YORBA ST. / CARROLL WAY.

NO
LOCATION
MAP