

GPS #: **1198**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 708/A-5

City / Location: Whittier, Los Angeles Co.

Scale Factor: 1.00000860

Ellipsoid Red. Factor: 0.99999272

Combination Factor: 1.00000140

Convergence Angle: -00 57 13.08423

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 55 58.97937	117 59 07.45118	2287520.878	6035275.002	151.962
2007.00	33 55 58.99557	117 59 07.46850	2287522.54	6035273.57	

References: L.A. RSB MM 654/87-77

Description:

FD PUNCHED SPIKE AND OCS BRASS TAG STAMPED "GPS 1198" FLUSH IN A.C. PER L.A. CO. TR. 24939 MM 654/87-88. STATION IS LOCATED 421'+/- N'LY FROM THE INTER OF LEFFINGWELL RD. AND FIRST AVE.

