

GPS #: 1200R1

Date Destroyed:

Date Revised: 2/22/2010

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 708/B-5

City / Location: La Habra

Scale Factor: 1.00000870

Ellipsoid Red. Factor: 0.99999050

Combination Factor: 0.99999925

Convergence Angle: -00 56 44.88953

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 56 00.06592	117 58 16.14308	2287559.042	6039599.488	
2007.00	33 56 00.08218	117 58 16.16048	2287560.71	6039598.05	

References: CITY OF LA HABRA TRACT 1943, CR 2001-0687, CR 2010-0082

Description:

FD GEAR SPIKE AND WASHER WITH TAG STAMPED "LS 5411", IN LIEU OF PUNCHED SPIKE AND WASHER (ILLEGIBLE) AND TIN, DOWN 0.05' LOCATED 3' W'LY OF THE E'LY END OF THORNE AVE. (BOUNDARY FOR TRACT 1943), AND ALONG THE CENTERLINE OF THORNE AVE.

