

GPS #: **1203**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 708/B-5

City / Location: La Habra

Scale Factor: 1.00000970

Ellipsoid Red. Factor: 0.99998969

Combination Factor: 0.99999949

Convergence Angle: -00 56 55.50448

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 56 20.73649	117 58 35.45994	2289675.215	6038006.659	215.252
2007.00	33 56 20.75272	117 58 35.47735	2289676.88	6038005.22	

References: RS 92-1117, CR 1397

Description:

FD PUNCHED SPIKE AND 1 1/4" OCS BRASS TAG STAMPED "GPS 1203" SET IN POUR ROCK, FLUSH IN A.C. LOCATED ALONG THE APPARENT CENTERLINE OF VALLEY HOME AVE., 87'+/- N'LY FROM ITS INTER WITH FOXDALE AVE.

