

GPS #: **1217**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 993/A-7

City / Location: San Clemente

Scale Factor: 0.99995491

Ellipsoid Red. Factor: 1.00000440

Combination Factor: 0.99995935

Convergence Angle: -00 44 43.70207

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 24 19.05521	117 36 23.74200	2093788.481	6147671.077	-92.772
2007.00	33 24 19.07215	117 36 23.75721	2093790.21	6147669.81	

References: OCS SURVEY FILE # M92-15

Description:

FD LEAD AND BRASS NAIL WITH 1 1/4" OCS BRASS TAG STAMPED "MLLW AZ MK", FLUSH, LOCATED FROM THE AVENIDA CALIFIA OFF-RAMP FROM THE SOUTH BOUND I-5 FREEWAY, PROCEED SW'LY ALONG CALIFIA 0.5 MILE TO THE BEACH PARKING AREA. PARK CLOSE TO CONC. SIDEWALK BEACH ACCESS. HIKE 75'+/- W'LY TO END OF SIDEWALK AND STATION AT LEFT EDGE OF WALK, E'LY OF RAILS.

