

**GPS #:** 1220

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 992/H-5

City / Location: San Clemente

Scale Factor: 0.99995534

Ellipsoid Red. Factor: 1.00000430

Combination Factor: 0.99995967

Convergence Angle: -00 45 15.97472

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 25 22.87890	117 37 22.47107	2100304.011	6142777.830	-90.521
2007.00	33 25 22.89583	117 37 22.48644	2100305.74	6142776.55	

References: OCS SURVEY FILE # M92-15

## Description:

FD 2" I.P. WITH PUNCHED SPIKE & OCS WASHER STAMPED "MLLW-8 11-94", LOCATED FROM THE AVENIDA PALIZADA OFF-RAMP OF THE SOUTH BOUND I-5 FREEWAY, PROCEED SW'LY ALONG PALIZADA 0.5 MILE TO STOP AT ENCINO LN. ON RIGHT WITH CALLE SEVILLE ON LEFT. TURN RIGHT AND CONTINUE SW'LY ALONG ENCINO LN. 0.1 MILE TO FORK WITH LINDA LN. ON RIGHT. TAKE RIGHT FORK ONTO LINDA LN. AND CONTINUE 0.2 MILE TO END OF LINDA LN. AND PARK. STATION IS 70'+/- W'LY OF THE RADIUS POINT OF THE CUL-DE-SAC, 20'+/- S'LY OF THE A.C. DR. TO THE RAILRD. CROSSING.

