

GPS #: 1225

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 992/C-1

City / Location: Dana Point

Scale Factor: 0.99995629

Ellipsoid Red. Factor: 1.00000430

Combination Factor: 0.99996062

Convergence Angle: -00 46 36.73938

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 27 10.94757	117 39 49.44481	2111392.464	6130470.229	-90.400
2007.00	33 27 10.96456	117 39 49.46066	2111394.20	6130468.91	

References: OCS SURVEY FILE # M92-15

Description:

FD PUNCHED SPIKE AND OCS WASHER STAMPED "PCH 20 87AO" FLUSH IN A.C., LOCATED FROM THE INTER OF PALISADES DR. AND P.C.H., PROCEED 0.3 MILE SE ALONG P.C.H. TO SAID MONUMENT BEING ON THE SW SIDE OF P.C.H., 6'+/- FROM THE EDGE OF PAVEMENT.

