

**GPS #:** **1226**

Date Destroyed:

Date Revised: 5/13/2014

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 972/B-7

City / Location: Dana Point

Scale Factor: 0.99995655

Ellipsoid Red. Factor: 1.00000460

Combination Factor: 0.99996116

Convergence Angle: -00 46 59.65517

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 27 36.10323	117 40 31.14646	2113982.936	6126972.088	-96.417
2007.00	33 27 36.12010	117 40 31.16242	2113984.66	6126970.76	

References: OCS SURVEY FILE # M92-15

**Description:**

FD LEAD AND TACK WITH TAG STAMPED "SS10" FLUSH IN CONC. SIDEWALK, LOCATED FROM THE INTER OF DOHENY PARK RD. AND P.C.H., PROCEED SE ALONG P.C.H. 1400'+/- TO STATION LOCATED AT THE APPARENT CENTER OF AN AERIAL TARGET. MIDDLE OF SIDEWALK SOUTHWESTERLY SIDE OF PCH AT 34600 PACIFIC COAST HWY. 30'+/- NORTHEAST OF CULVERT PIPE UNDER RAILROAD TRACKS.

