

GPS #: 1228

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 971/H-7

City / Location: Dana Point

Scale Factor: 0.99995666

Ellipsoid Red. Factor: 1.00000500

Combination Factor: 0.99996169

Convergence Angle: -00 47 57.45575

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 27 46.12229	117 42 16.33069	2115118.576	6118075.910	-105.101
2007.00	33 27 46.13916	117 42 16.34680	2115120.30	6118074.57	

References: OCS SURVEY FILE # M92-15

Description:

FD LEAD AND TACK WITH OCS TAG FLUSH IN CONC. SIDEWALK, LOCATED FROM THE INTER OF PACIFIC COAST HWY. AND DANA POINT HARBOR DR., PROCEED 1.1 MILES W'LY ALONG THE DR. TO THE ENTRANCE TO A PARKING LOT ON THE S'LY SIDE. PARK AT THE NEAREST RESTROOM IN THE PARKING LOT. STATION IS LOCATED 100' S'LY IN THE CONC. SIDEWALK, 2' FROM THE SEA WALL WHICH HAS "C-53" STENCILED IN BLACK PAINT NEAR STATION.

