

**GPS #:** 1235

**Date Destroyed:** 1/1/1998  
**Date Revised:** 7/16/1996  
**Benchmark Designation:**  
**OCS Index Map:** 5LB  
**Page/Grid:** 862/A-4  
**City / Location:** Unin., Orange County

**Scale Factor:** 0.99997297  
**Ellipsoid Red. Factor:** 0.99996819  
**Combination Factor:** 0.99994116  
**Convergence Angle:** -00 47 03.22471

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 09.93749	117 40 37.64224	2196243.169	6127547.715	664.726
2007.00	33 41 09.95423	117 40 37.65808	2196244.88	6127546.40	

**References:** CR 0541

**Description:**

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 2" I.P. WITH TACK AND TAG STAMPED "LS 4965", FLUSH WITH GROUND, LOCATED FROM THE OVERPASS AT ALTON PKWY. AND THE FOOTHILL TRANSPORTATION CORRIDOR, PROCEED NW'LY ALONG THE CORRIDOR 0.4 +/- MILE TO THE ANGLE POINT IN THE BARBED WIRE FENCE ON THE NE'LY SIDE OF THE RD. PROCEED NE'LY ALONG THE FENCE 415'+/- TO ANOTHER ANGLE POINT IN THE FENCE AND THE LOCATION OF SAID POINT.