

**GPS #:** **1237**

**Date Destroyed:** **7/25/2000**

**Date Revised:**

**Benchmark Designation:**

**OCS Index Map:** **5LB**

**Page/Grid:** **832/D-7**

**City / Location:** **Unin., Orange County**

**Scale Factor:** **0.99997570**

**Ellipsoid Red. Factor:** **0.99993237**

**Combination Factor:** **0.99990808**

**Convergence Angle:** **-00 46 10.52055**

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 38.67423	117 39 01.73236	2205102.046	6135771.861	1413.104
2007.00	33 42 38.69080	117 39 01.74828	2205103.74	6135770.54	

**References:** **OCS SURVEY FILE # OC94/5-20N**

**Description:**

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 1 1/2" I.P. WITH WOODEN PLUG AND NAIL, UP 0.3', LOCATED FROM THE INTER OF SANTIAGO CANYON RD. AND MOJESKA CANYON RD., PROCEED 0.3 MILE N'LY ALONG SANTIAGO CANYON RD. TO HANGMANS TREE RD. (A DIRT RD.). TURN LEFT ALONG SAID RD. AND PASS THRU A LOCKED GATE (DA-1 LOCK) AND CONTINUE W'LY 0.8 MILE ACROSS THE CREEK AND UPHILL TO THE RIDGE RD. TURN LEFT ON RIDGE RD. AND GO SE'LY 0.5 MILE TO A FORK IN THE RD. STAY TO THE RIGHT AND CONTINUE ALONG RIDGE RD. 0.1 MILE TO A LOCKED GATE (OC FIRE LOCK). PASS THRU GATE AND PROCEED 0.4 MILE TO BOLERO LOOKOUT RD., TURN LEFT AND GO SE'LY 0.3 MILE TO A GATE AND PARK. HIKE FROM THE NE'LY END OF THE GATE 2000' NE'LY ALONG FENCE TO SAID STATION LOCATED ON THE RIDGE TOP. TO ARRANGE ACCESS, CONTACT PETE KATALARIS AT-WORK (818) 962-7372, AND HOME (714) 649-2398.