

GPS #: **1239**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 862/E-1

City / Location: Unin., Orange County

Scale Factor: 0.99997484

Ellipsoid Red. Factor: 0.99992986

Combination Factor: 0.99990470

Convergence Angle: -00 45 50.83400

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 11.56749	117 38 25.90721	2202321.810	6138761.431	1465.709
2007.00	33 42 11.58413	117 38 25.92288	2202323.51	6138760.13	

References: OCS SURVEY FILE # OC94/5-20N

Description:

FD 6" X 6" CONC. POST WITH STEEL PIN @ CENTER, UP 0.8', LOCATED FROM THE SE CORNER OF SANTIAGO CANYON RD. AND GERTNER ESTATE RD., HIKE S'LY UP THE CUT SLOPE ON THE EAST SIDE OF SANTIAGO CANYON RD. TO A RIDGE WITH A BARBED WIRE FENCE. CONTINUE E'LY UP THE RIDGE ALONG THE BARBED WIRE FENCE 450'+/- TO SAID STATION.

