

GPS #: **1241**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 891/J-7

City / Location: Mission Viejo

Scale Factor: 0.99996592

Ellipsoid Red. Factor: 0.99998293

Combination Factor: 0.99994886

Convergence Angle: -00 47 14.60719

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 45.21348	117 40 58.35583	2169511.547	6125429.860	356.617
2007.00	33 36 45.23043	117 40 58.37196	2169513.28	6125428.52	

References: MM 357/20-23

Description:

FD 2 1/4" PUNCHED ALUMINUM OCS DISK STAMPED "9-74" DOWN 1.7' IN OCS WELL MONUMENT LOCATED AT THE INTER OF THE RANCHO TRABUCO LINE AND THE CENTERLINE OF ALICIA PKWY., 416.62' NE'LY FROM THE CENTERLINE INTER OF ALTHEA AVE. AND ALICIA PKWY.

