

**GPS #:** 1244

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 891/J-7

City / Location: Mission Viejo

Scale Factor: 0.99996588

Ellipsoid Red. Factor: 0.99998434

Combination Factor: 0.99995022

Convergence Angle: -00 47 10.85267

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

NO PHOTO

| Epoch Adjustment | Latitude       | Longitude       | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35          | 33 36 43.47466 | 117 40 51.52344 | 2169327.871   | 6126005.220  | 327.234               |
| 2007.00          | 33 36 43.49157 | 117 40 51.53956 | 2169329.60    | 6126003.88   |                       |

References: MM 366/48-50

**Description:**

FD 1" I.P. WITH TACK AND 3/4" BRASS TAG  
STAMPED "RCE 15822" DOWN 0.2', LOCATED 480'+/-  
S'LY OF THE CENTERLINE OF ALICIA PKWY. AND  
ALONG THE NW'LY RIGHT OF WAY OF THE A.T. &  
S.F. RAILRD., AT THE CORNER OF LOTS 10 & 11 OF  
TRACT # 8800, 0.8' NE'LY OF A CHAIN LINK FENCE  
CORNER.

