

GPS #: 1245

Date Destroyed: 7/25/2000

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 891/J-7

City / Location: Mission Viejo

Scale Factor: 0.99996651

Ellipsoid Red. Factor: 0.99998577

Combination Factor: 0.99995228

Convergence Angle: -00 47 26.97750

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 09.89463	117 41 20.86703	2172032.264	6123560.664	297.253
2007.00	33 37 09.91171	117 41 20.88310	2172034.01	6123559.33	

References: CR 0015

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 2 1/2" OCS PUNCHED BRASS DISK STAMPED "TRABUCO NO. 3 RESET 6-5-79" DOWN 1.0', LOCATED BETWEEN LOS ALISOS BLVD. AND ALISO CREEK, 190'+/- W'LY FROM THE CENTERLINE INTER OF LOS ALISOS BLVD. AND BRUSSELS AVE., 15'+/- NW'LY FROM THE NW'LY EDGE OF THE BIKE TRAIL, AND 700'+/- W'LY OF THE CENTERLINE OF THE A.T. & S.F. RAILRD.