

GPS #: 1258

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 741/A-6

City / Location: Anaheim

Scale Factor: 0.99999849

Ellipsoid Red. Factor: 0.99998962

Combination Factor: 0.99998811

Convergence Angle: -00 49 27.97107

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 52 27.20753	117 45 01.04847	2265009.122	6106277.047	216.906
2007.00	33 52 27.22403	117 45 01.06486	2265010.81	6106275.69	

References: CR 0926

Description:

FD 2" I.P. WITH 1 1/4" BRASS OCS TAG, STAMPED "GPS 1258" (AKA O.C.F.C.D. E01 SCOUR MONUMENT, STATION 1198+05.2), LOCATED FROM THE INTER OF WEIR CANYON BLVD. AND LA PALMA AVE., PROCEED SW'LY ALONG LA PALMA AVE. TO YORBA LINDA REGIONAL PARK, ENTER THE PARK AT ITS MOST N'LY MAINTENANCE DR.WAY ENTRANCE AND CONTINUE SE'LY ALONG SAID RD. TO THE SANTA ANA RIVER BIKE TRAIL, CONTINUE N'LY ALONG BIKE TRAIL TO A CONC. DROP STRUCTURE. THE MONUMENT IS LOCATED IN THE N'LY END OF SAID STRUCTURE IN CONC.

