

GPS #: 1259

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 741/A-6

City / Location: Anaheim

Scale Factor: 0.99999863

Ellipsoid Red. Factor: 0.99998955

Combination Factor: 0.99998818

Convergence Angle: -00 49 25.21457

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 52 30.24487	117 44 56.03227	2265310.040	6106704.373	218.238
2007.00	33 52 30.26138	117 44 56.04861	2265311.73	6106703.02	

References: CR 0927

Description:

FD 2" I.P. WITH 2" BRASS CAP STAMPED "O.C.F.C.D. R/W ANGLE PT" L.S. 3522 BM E01-V1-20", DOWN 0.1', LOCATED FROM THE INTER OF WEIR CANYON BLVD. AND LA PALMA AVE., PROCEED SW'LY ALONG LA PALMA AVE. TO YORBA LINDA REGIONAL PARK, ENTER THE PARK AT ITS MOST N'LY MAINTENANCE DR. WAY ENTRANCE AND CONTINUE SE'LY ALONG SAID RD. TO THE SANTA ANA RIVER BIKE TRAIL, CONTINUE N'LY ALONG BIKE TRAIL CONTINUE ON UNDER WEIR CANYON RD. BRIDGE TO A FORK IN THE TRAIL, NOW DIRT, CONTINUE ALONG APPROX. 200' TO A PADDLE POST, THE MONUMENT IS LOCATED 1' DOWN IN DIRT 4' W'LY OF HINGE POINT.

