

**GPS #:** 1261

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 741/A-6

City / Location: Anaheim

Scale Factor: 0.99999898

Ellipsoid Red. Factor: 0.99998743

Combination Factor: 0.99998642

Convergence Angle: -00 49 24.10636

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 52 38.00916	117 44 54.01556	2266092.377	6106885.677	262.559
2007.00	33 52 38.02570	117 44 54.03194	2266094.07	6106884.32	

References: CR 0929

**Description:**

FD PUNCHED SPIKE AND BRASS OCS TAG FLUSH IN A.C. BIKE TRAIL, LOCATED FROM THE INTER OF WEIR CANYON RD. AND LA PALMA AVE., PROCEED NE'LY ALONG LA PALMA AVE. AND TURN RIGHT INTO A CONC. DR.WAY (JUST NORTH OF POWER POLES AND BEGINNING OF ANAHEIM WETLANDS AREA) THE MONUMENT IS LOCATED IN THE S'LY EDGE OF PAVEMENT OF BIKE TRAIL AND DR.WAY, SET IN A.C. FLUSH.

