

GPS #: 1262

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 889/C-7

City / Location: Newport Beach

Scale Factor: 0.99996647

Ellipsoid Red. Factor: 1.00000500

Combination Factor: 0.99997154

Convergence Angle: -00 54 18.79551

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 08.12944	117 53 50.28440	2172791.823	6060190.333	-106.132
2007.00	33 37 08.14590	117 53 50.30143	2172793.51	6060188.92	

References: CR 0930

Description:

FD LEAD AND 1 1/4" OCS BRASS TAG STAMPED "GPS 1262 1-95" WITH BRASS NAIL FLUSH IN CONC. SIDEWALK, LOCATED FROM THE INTER OF PACIFIC COAST HWY. AND BAYSIDE DR., PROCEED NE'LY TO BAYSIDE VILLAGE TRAILER PARK. TURN LEFT AND CONTINUE ALONG TO THE "CLUB HOUSE" AND CONTACT MAIN DESK FOR A "GATE CARD". RETURN BACK TO BAYSIDE DR. AND TURN LEFT TO THE "ENTRANCE GATE" AND CONTINUE THROUGH AND TAKE THE FIRST LEFT INTO THE MARINA PARKING LOT. PROCEED THROUGH THE PARKING LOT TO DOCK "A" AND SAID MONUMENT LOCATED APPROX. 30' TO THE LEFT AND SET IN A CONC. SIDEWALK, IN UPPER NEWPORT BAY MARINA.

